

**MARYLAND HISTORICAL TRUST  
DETERMINATION OF ELIGIBILITY FORM**

NR Eligible: yes ☐  
no ☐

Property Name: Smith-Molesworth Farmstead Inventory Number: F-5-097  
Address: 12403 Lee Hill Drive Historic district: ☐ yes ☒ no  
City: Mount Airy Zip Code: 21770 County: Frederick  
USGS Quadrangle(s): Damascus  
Property Owner: Myers, Marvin J., Jr., and Virginia J. Myers Tax Account ID Number: 234039  
Tax Map Parcel Number(s): 189 Tax Map Number: 89-8  
Project: PATH Kemptown Substation Agency: FERC  
Agency Prepared By: GAI Consultants, Inc.  
Preparer's Name: Matthew G. Hyland Date Prepared: 12/2/2008  
Documentation is presented in: Phase I Cultural Resources Survey, Kemptown Substation, Potomac-Appalachian Transmission Highline Project  
Preparer's Eligibility Recommendation: ☒ Eligibility recommended ☐ Eligibility not recommended  
Criteria: ☒ A ☐ B ☒ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G  
*Complete if the property is a contributing or non-contributing resource to a NR district/property:*  
Name of the District/Property: \_\_\_\_\_  
Inventory Number: \_\_\_\_\_ Eligible: ☐ yes ☐ no Listed: ☐ yes ☐ no  
Site visit by MHT Staff ☐ yes ☒ no Name: \_\_\_\_\_ Date: \_\_\_\_\_

**Description of Property and Justification:** *(Please attach map and photo)*

The Smith-Molesworth Farmstead features a dwelling and numerous agricultural outbuildings, which maintain sufficient integrity to convey their significance. The primary resource at this property is the dwelling a cross-gable, frame vernacular style two-story building standing on a continuous concrete foundation. The building dates from circa 1870, with a circa 1925 date assigned to the front block, according to MHT survey data and historic mapping. A two-story, gable roof addition extends from the rear of the building. Exterior materials include asbestos shingle siding, Dutch lap wood siding, cornerboards, and new vinyl shutters. The façade features a half-hipped, full-length, three-bay-wide, one-story front porch with turned posts. Three-tab, standard strip asphalt shingles have replaced the standing seam metal roofing identified in the 1994 survey. The fenestration consists of paired, one-over-one, double-hung, wood sash windows with mullions and metal storm windows on the front block of the house, and two-over-two, double-hung wood sash windows on the rear extension. On both eave walls of the rear extension, enclosed porches have been appended: a shed-roof side porch on the southeast elevation and a gable-roof porch on the northwest elevation. Both enclosed porches appear to date from the second half of the twentieth century. The gable ends feature cornice returns. An exterior brick chimney stack (not original) stands against the southeast elevation. A brick stove flue stands against the exterior of the gable end of the rear addition. A two-bay-wide contemporary, frame, gable-roof garage stands at the rear of the driveway. This property, which functioned as a dairy farm, contains a collection of agricultural buildings that include a heavy timber frame

**MARYLAND HISTORICAL TRUST REVIEW**

Eligibility recommended ☐ Eligibility not recommended ☒  
Criteria: ☐ A ☐ B ☐ C ☐ D Considerations: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

MHT Comments: Undistinguished example of a common property type

Jonathan Sage  
Reviewer, Office of Preservation Services

10/6/09  
Date

B. Kuntz  
Reviewer, National Register Program

10/6/09  
Date

200902783

bank barn, a meat house, a poultry shelter, a hog shelter, a masonry milk house, a granary, a machine/equipment shed, and a wagon shed. The heavy timber frame bank barn stands on a continuous stone foundation. Vertical wood siding and plywood sheets cover the exterior. Corrugated metal has been installed on the gable roof. Window apertures have been cut into the exterior wall above the forebay. A small section of the forebay and feed lot has been enclosed. A one-story, masonry, gable-roof, milk house has been appended to the northwest elevation of the barn.

The frame granary has been altered. The granary's entry portal has been enclosed and reduced to make the building a garage or workshop. The granary has a corrugated sheet metal roof and board-and-batten wood siding. A frame privy stands between the granary and the barn. A machine/equipment shed and a wagon shed stand between the granary and the dwelling. The wagon shed has asphalt shingle roofing and board-and-batten wood siding. Like the granary, the wagon shed has been altered at its entry and exit portals.

The machine/equipment shed, a frame building with a metal roof, features a pent-shed roof and an open façade and may date from the second half of the twentieth century. The meat house, a poultry shelter, a hog shelter are small, one-story frame buildings that stand to the rear of the dwelling. The poultry shelter and the hog shelter have shed roofs and wood siding. The meat house has a gable roof and wood siding. Viewed from the roadway, no changes in the integrity of the property as noted in 1994 were observed. George M. Smith and James W. Smith built the farmstead in the 1870s. Anna Maria Molesworth acquired the farm in 1896, according to MHT survey data. Historic mapping (Lake 1873) locates the G. Smith farm at this location. Smith does appear in the annals of Frederick County local history (William and McKinsey 1979) but not as a prominent individual. Further directed historical research and survey is warranted to establish the NRHP eligibility of this property.

MHT's 1994 survey data for the Smith-Molesworth Farmstead asserts that the property is minimally significant for its architecture, in that it reflects the local agricultural and historic development from circa 1875 to the 1940s as a typical Frederick County farm of the period. However, intensive development of the surrounding landscape into residential subdivisions has occurred since the 1994 survey. With the decreasing number of intact examples of Frederick County farms taken into consideration, the significance of the Smith-Molesworth Farmstead has increased. As a rare example, the farmstead reflects trends in local agricultural history and continues to convey an association with the growth and historic development of the area. Additionally, the farm contains noteworthy examples of domestic and agricultural architecture that collectively are significant at the local level. Therefore, the Smith-Molesworth farmstead is recommended NRHP eligible under Criteria A and C at the local level. Additional survey work with property owner permission is recommended in order to delineate a NRHP boundary and evaluated the individual eligibility of contributing resources within the property.

This reconnaissance-level survey was limited to views of the property from the public right-of-way and information found in existing survey data due to no permission to enter the property granted by the owner. Therefore, a comprehensive update of the entire property cannot be provided at this time, but a description of buildings adjacent to the roadway is sufficient to support a recommendation for NRHP eligibility.

**MARYLAND HISTORICAL TRUST REVIEW**


Eligibility recommended \_\_\_\_\_

Eligibility not recommended \_\_\_\_\_

Criteria: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D Considerations: \_\_\_ A \_\_\_ B \_\_\_ C \_\_\_ D \_\_\_ E \_\_\_ F \_\_\_ G

MHT Comments:

\_\_\_\_\_  
Reviewer, Office of Preservation Services\_\_\_\_\_  
Date\_\_\_\_\_  
Reviewer, National Register Program\_\_\_\_\_  
Date



gai consultants

SMITH-MOLESWORTH FARMSTEAD (F-5-997)

SITE PLAN

PROPOSED KEMPTOWN SUBSTATION  
PATH PROJECT, POWER ENGINEERS, INC.

DWN: MLO CHKD: MGH

APPD. DATE: 12/02/08

SCALE: NOT DRAWN TO SCALE


DRAWING NUMBER C080942.00



## FIGURE

NRHP BOUNDARY OF SMITH-  
MOLESWORTH FARMSTEAD (F-5-097)  
PATH PROJECT  
PROPOSED KEMPTOWN SUBSTATION  
POWER ENGINEERS, INC.





SOURCE: USGS DAMASCUS, MD, QUADRANGLE MAP  
(1944, PHOTOREVISED 1993)



gai consultants



## FIGURE

LOCATION OF SMITH-MOLESWORTH  
FARMSTEAD (F-5-097)

PATH PROJECT

PROPOSED KEMPTOWN SUBSTATION  
POWER ENGINEERS, INC.



7-5-097

Smith-Melloworth Farmstead

Frederick County  
Sterling, La Verne

18 October 2008  
House facing W





7-5-77

Smith-Molesworth Farmstead

Frederick County

Strong. Saver

8 October 2008

House and Garage facing SW

NOS



7-5-97

Smith Holloworth Farmstead

Frederick County

Steve J. Larrier

8 to 1000

House and Shed facing SSW



F-5-97

Smith Malesworth Farm - Cal

Frederick County, Maryland  
Spray Larder

8 October 2008

House and Garage facing S W





7-5-97

Smith-Molesworth farmstead  
2403 - in 11th Dr.

Frederick County,  
Steve. Larner

8 October 2008  
Barren - facing SE

NOS



7-5-197

Smith Bloisworth Farmstead

Fredrick County

Shed, Sinner

8 October 2008

Barn - facing W & W





F-5-097

Smith Holloworth farmstead

Frederick County

Stony, Sarnes

8 October 2008

Overview facing ECU



F - 5 - 197

Smith-Molesworth Farmstead  
1203 Lee Hill Dr.  
Frederick County  
Steve Saver  
8 October 2005  
Schweitzer Barn facing ESE



7-5-97

Smith-Moisesworth Farmstead

Frederick County

Steve, Larner

8 Oct 2008

Orange, Virginia





# 5. - 77

Smith Mollen or the farmstead

Frederick County

Steve D. Lander

8 October 2008

House facing SSW



7-5-97

9 Smith Meadows Farmstead  
12403 Lee Hill Drive

Frederick County

Steve J. Sauer

8 October 2008

Sweetzer Barn facing NW

F-5-97

Smith-Molesworth Farmstead

Monrovia vicinity

Private

Ca. 1875-1940

The Smith-Molesworth Farmstead is minimally significant in architecture as an example of a typical late 19th century farmstead with additions being made through the period about 1875 to 1940. These reflect the changing production of the farm from grain to dairy products in the early 20th century. The dwelling has a circa 1925-1930 main section adjoining a rear wing which may date from 1875. The principal traces of the earlier house are in the 2/2 sash of the wing and German siding of different character from the front section's cladding. Other buildings in the farmstead include a frame meathouse, a hog barn, a chicken house, an equipment shed, a frame and stone bank barn with an adjoining concrete block milk house and a wagon shed/corn crib. These outbuildings range in date from about 1875 to 1940. The barn has a partially enclosed stall level which was used as a milking parlor, a common adaptation of older barns to dairy production in the early 20th century. The farmstead was first established by George M. and James W. Smith about 1871. In 1896, the Molesworth family bought the property, which encompassed 155 acres of the original 160-acre Smith farm. The Molesworths were the owners until 1957.

F-5-97  
Smith-Molesworth Farmstead  
Monrovia  
Frederick County

HISTORIC CONTEXT:

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Piedmont  
(Harford, Baltimore, Carroll, Frederick, Howard, Montgomery  
Counties, and Baltimore City)

Chronological/Development Period:  
Industrial/Urban Dominance, A.D. 1870-1930  
Modern Period, A.D. 1930-Present

Prehistoric/Historic Period Themes:  
Architecture, Landscape Architecture and Community Planning

Resource Types:

Category: Building

Historic Environment: Suburban

Historic Function and Use:  
Domestic/single dwelling/residence  
Domestic/secondary structure/other dependencies  
Agriculture/subsistence/animal facility/barn  
Agriculture/subsistence/storage/granary  
Agriculture/subsistence/agricultural outbuilding

Known Design Source: None

# MARYLAND INVENTORY OF HISTORIC PROPERTIES

## Maryland Historical Trust State Historic Sites Inventory Form

Survey No. F-5-97

Magi No.

DOE ☐ yes ☒ no

### 1. Name (indicate preferred name)

historic Smith-Molesworth Farmstead

and/or common

### 2. Location

street & number 12403 Lee Hill Drive ☐ not for publicationcity, town Monrovia ☒ vicinity of congressional district 6th

state Maryland county Frederick

### 3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input checked="" type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

### 4. Owner of Property (give names and mailing addresses of all owners)

name Marvin J., Jr., and Virginia J. Myers

street &amp; number 12403 Lee Hill Drive telephone no.:

city, town Monrovia state and zip code MD 21770

### 5. Location of Legal Description

courthouse, registry of deeds, etc. Frederick County Courthouse liber 1086

street &amp; number 100 W. Patrick Street folio 98

city, town Frederick state MD 21701

### 6. Representation in Existing Historical Surveys

title

date ☐ federal ☐ state ☐ county ☐ local

depository for survey records

city, town state

## 7. Description

Survey No. F-5-97

### Condition

☐ excellent  
☒ good  
☐ fair

☐ deteriorated  
☐ ruins  
☐ unexposed

### Check one

☐ unaltered  
☒ altered

### Check one

☒ original site  
☐ moved      date of move \_\_\_\_\_

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

CONTRIBUTING RESOURCE COUNT: 9

The Smith-Molesworth Farmstead is centered on a two-story frame dwelling built in the second quarter of the 20th century with an adjoining rear wing possibly built about 1875 and its associated outbuildings which include a frame bank barn and a milk house, a milk can washing shed, a wagon shed/corn crib, a meathouse, a hog pen, a machine shed, and a chicken house located on the south side of Lee Hill Drive about 750 feet east of Bartholows Road near Monrovia, Frederick County, Maryland. The farmstead is located in a modern subdivision built on the former agricultural fields associated with its original 160-acre tract. The farmstead is currently principally a private residence, but it still partially in agricultural use. The dwelling faces north and the domestic outbuildings are located to the south, while the larger agricultural buildings are east of the house. The outbuildings range in date from about 1875 to about 1940. Dates of the structures are based on architectural evidence, a personal interview with the current owner, Mr. Marvin J. Myers, Jr., land records, and historical maps.

The dwelling's main section is the early 20th century part and is a frame building with german siding and two principal bays on the north elevation. The main entrance is an off-center door with a glass panel upper section. A one-story porch crosses the elevation. The windows are paired 1/1 sash with replacement shutters. The gable roof is corrugated metal. A patch at the center shows where the original chimney was located. In recent years, the chimney was replaced by an exterior brick stack on the east gable end. A two-story rear wing possibly built between 1875 and 1900 extends from the southwest corner and has asbestos shingle siding on the south elevation. An enclosed one-story porch is on the east side and above this porch are two second-story windows with 2/2 sash, indicating the earlier construction date than the main section. The german siding on this wall is also of an earlier period than that on the main section. An exterior brick chimney is on the south end of the wing and on the west side is a 1970's one-story addition which was used as an office by a previous owner. The interior of the house has been much altered and modernized in the past 20 years.

### Domestic outbuildings:

Meathouse, hog pen, chicken house: These three frame outbuildings are located south of the dwelling near a non-contributing modern garage. They each have vertical and/or board and batten siding. The chicken house has a shed corrugated metal roof and faces south. The hog barn has a standing seam metal roof and also faces south, but has been adapted for use as a storage shed, with a section of the north wall removed. The meat house has a four-panel door in the north gable end and a composition shingle roof. The outbuildings appear to date from the last quarter of the 19th century and the first decade of the 20th century.

### Agricultural outbuildings:

Equipment shed: The one-story frame equipment shed located east of the house the domestic outbuildings resembles a small garage, with vertical and board and



## 8. Significance

Survey No. F-5-97

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates C. 1875-1940

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☒ C ☐ D  
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☒ local

Prepare both a summary paragraph of significance and a general statement of history and support.

The Smith-Molesworth Farmstead is minimally significant in architecture as a representative of the typical late 19th century farmstead in Frederick County, retaining the principal structures of a dwelling, a bank barn, a wagon shed/corn crib, and a selection of small domestic and agricultural outbuildings. The functional style of the buildings is also representative, their only unifying element being the red paint and white trim of the outbuildings. The farmstead's setting in a modern subdivision tends to magnify the agricultural appearance of the group, although most of the buildings are adapted for other uses. The original farmstead, of which the rear wing of the house, the stone foundation of the barn, and perhaps some of the outbuildings are the only remaining structures, was built by George M. and James W. Smith. G. Smith is the name shown on the 1873 Titus Atlas map. In 1885, George Smith sold the farm to Sarah Bartholow and in 1896, Anna Maria Molesworth acquired the property. The farm remained in the Molesworth family until 1957.

## 9. Major Bibliographical References

Survey No. F-5-97

Holdcraft, Jacob M. Names In Stone, V.2. Privately published, Ann Arbor, Mi., 1966, p. 808.

Land Records of Frederick County

Myers, Mr. Marvin J., Jr. , personal interview, April 20, 1994

Titus, C.O. Atlas of Frederick County, 1873

## 10. Geographical Data

Acreage of nominated property 5 acres

Quadrangle name Damascus, Md.

Quadrangle scale 1:24000

UTM References do NOT complete UTM references

A 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

B 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

C 

--	--	--	--	--	--	--	--	--	--

D 

--	--	--	--	--	--	--	--	--	--

E 

--	--	--	--	--	--	--	--	--	--

F 

--	--	--	--	--	--	--	--	--	--

G 

--	--	--	--	--	--	--	--	--	--

H 

--	--	--	--	--	--	--	--	--	--

### Verbal boundary description and justification

Concurrent with Tax Map 89, Parcel 189

### List all states and counties for properties overlapping state or county boundaries

state	code	county	code
-------	------	--------	------

state	code	county	code
-------	------	--------	------

## 11. Form Prepared By

name/title Janet L. Davis, Historic Sites Surveyor

organization Frederick County Planning & Zoning Dept. date June 1994

street & number 12 E. Church Street telephone 696-2958

city or town Frederick state MD 21701

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust  
Shaw House  
21 State Circle  
Annapolis, Maryland 21401  
(301) 269-2438

MARYLAND HISTORICAL TRUST  
DHCP/DHCD  
100 COMMUNITY PLACE  
CROWNSVILLE, MD 21032-2023  
514-7600

### 7.1 Description (Continued)

batten siding and off-center double swing doors on the east gable end. The doors are flanked on the right by a small flush board door to a storage area on the north side. The roof is covered with composition shingles. The shed was probably built about 1900-1920.

Wagon shed/corn crib: The wagon shed with corn cribs has been considerably altered on the interior for use as a workshop, with wallboard panels concealing the former cribs on the north and south sides. The exterior is still covered with vertical and board and batten siding, but the drive-through entrance on the west has been partially filled in to accommodate a modern lift-type door. The east end has been closed off. The roof is corrugated metal. The wagon shed was probably built about 1900.

Bank barn, milk house, and washing shed: The bank barn is the easternmost structure in the farmstead and its stone foundation is banked so that the forebay is on the south elevation. The stall level has been partially enclosed by concrete block as a milking parlor. The upper structure is covered with vertical tongue-and-groove siding and the roof is corrugated metal. The foundation may be older than the frame structure, which appears to date from about 1900. Sliding doors on the north elevation were replaced with plywood swing doors with cross bracing in recent years. Adjoining the barn on the west side is a small concrete block milk house with a composition shingle roof. This was probably built at the same time as the enclosure of the milking parlor in the barn, about 1925-1930. A single door is located in the west gable end of the milk house. Immediately west of the milk house is a small frame shed of about the same size, with vertical board siding and a corrugated roof with replaced sections of composition shingles. The shed's location and the existence of a water tap near the door on the south side indicates that its use was probably linked to the washing of milk cans used in the dairy operation. Its date is probably about 1925-1930.

12403 Lee Hill Drive


Liber/Folio	Grantee	Grantor	Lot Size, Description, Original Tracts, Miscellaneous	Cost
1086/98 23 May 79	Martin J., Jr. & Virginia J. Myers	Randall H. Gerlach, pers. rep. of estate of Charles M. Gerlach, dec.	Subdivision plat "Lingane View" Plat Book Section 7 6/167 House & 8 outbuildings shown on plat	\$145,000
<del>913/411</del> *955/587 6 Feb 75	Charles M. Gerlach	Georgia Ave. Properties, Inc.		
913/411 29 May 73	Charles M. Gerlach	Larry D. & Nancy Burdick Miller & Stanley J. Burdick	part of property conveyed to Georgia Ave. Properties by E. Brooke Lee 795/619 through atty-in fact Nancy B. Miller	
857/449 15 Sept 71	Stanley J. Burdick & Larry D. & Nancy B. Miller	Georgia Ave. Properties, Inc.		
795/619 30 Dec 68	Georgia Ave. Properties, Inc.	E. Brooke Lee & Nina S. Lee	part of "Hobbs Purchase" 78.342A.	
617/562 15 May 59	E. Brooke Lee	John E. Molesworth, Jr. & Margaret Done Molesworth	155 1/4 A. meadow	
575/522 3 Jan 57	John E. Molesworth & Margaret Done Molesworth	Reith S. Zimmerman		
575/521 30 Jan 57	Reith S. Zimmerman	Margaret Done Molesworth		
388/282 12 Aug 33	John E. Molesworth & Margaret Done Molesworth	Frank C. Norwood	155 1/4 A. meadow	
388/281 12 Aug 33	Frank C. Norwood	John E. & Margaret Done Molesworth	155 1/4 A.	


F-5-97

Liber/Folio	Grantee	Grantor	Cost
354/197 10 Jul 25	John R. Moler worth <del>old</del> Thomas B. Molerworth (brothers)	John R. Molerworth Actual heirs of Anna Maria (Clay) Molerworth	
JLJ 14/106 13 May 1896	Anna Maria (Clay) Molerworth	John B. Bartholow 155 1/4 A. (only child & heir at law of Sarah A. Bartholow, dec) et ux	\$3,100
AF 11/257 16 July 1885	Sarah A. Bartholow	George M. & Sarah Smith	157 3/4 A. part of "Hobbs Purchase" \$5,048
CM 7/198 4 May 1871	George M. & James M. Smith	George E. Tallott	AF 9/285, James Smith to George Smith part of "Hobbs Purchase" & "Land of Promise" 160 A. \$2,000
CM 6/517 31 Mar 1871	George E. Tallott	Joshua & Eliza Wood, Marry Tallott & Anna D. Tallott heirs of Samuel Tallott	160 A. \$2,500
ES 9/544 21 Jul 1857	Joshua & Eliza Wood & Elias Wood trustee (reverse names)	Samuel Tallott	Equity 2583



Scale 7 1/2 inches to the mile









F-5-97

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md.

North elevation

1/7



F-5-97

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md.

Southeast corner view

2/7



F-5-97

Smith - Molesworth Farmstead

Frederick County


Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md

Meathouse, chicken and hog pens, view  
from northeast

3/7



F-5-97

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md

Machine shed, east elevation

4/7





F-5-97

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md.

Wagon shed/corn crib, west elevation

5/7



F-5-97

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md.

Barn and milk house, view from northwest

6/7



F-5-77

Smith-Molesworth Farmstead

Frederick County

Photo: Janet Davis

April 1994

Neg. loc.: Md. SHPO, Crownsville, Md.

Barn, view from southeast

7/7